

Township 3 n., R. 37 E., W.M.

Chains	
28.25	Enter small timber and dense undergrowth.
34.50	Leave timber and undergrowth; steep, grassy descent, across bend of canyon-S.W.
37.25	Small, densely overgrown ravine-N.W.
38.75	Leave dense undergrowth; steep, grassy slope-N.20°W.
40.00	A point 400 ft. below the Sec. Cor. and set a Basalt Stone, 15 x 10 x 5 ins., 10 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; raise mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, N. of Cor. Pits impracticable. After careful search fail to find any trace of the old $\frac{1}{4}$ Sec. Cor., described by the Surveyor-General as a Stone, 20 x 12 x 4 ins., on N. side of Ravine. No trees.
42.25	Enter dense undergrowth.
49.25	Stream, 2 lks. wide, runs S. 70°W., thence along steep N. side of Ravine.
54.45	Leave dense undergrowth- steep slope S.
55.00	August 9: At this point I set off 15°50'30" on the Decl. Arc, and at 0H.5 M.P.M.; l.m.t., observe the sun on the meridian the resulting Lat. is 45° 41' 30".
69.00	Narrow strip of undergrowth, bears N.&.S.
75.25	Patch of undergrowth; bears N.&.S.
80.00	A point 350 ft. below the $\frac{1}{4}$ Sec. Cor. and set a Basalt Stone, 15 x 6 x 5 ins., 10 ins. in the ground, for Cor. of Secs. 33 & 34, marked with 3 notches on E.& W. edges; and raise mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high N. of Cor. Pits impracticable. The old Cor. of Secs. 33 & 34, a Basalt Stone, 18 x 12 x 10 ins., on S. face of Ridge, bears S.86 $\frac{1}{2}$ °W., 1 Ch. 28 lks. distant. I destroy all traces of this old Sec. Cor. Land; nearly level and mountainous. Soil; gravelly and stony, 3rd & 4th rate. Timber; scattering pine, fir and tamarack on first quarter.