

Chains	
26.50	Steep slope N.
30.00	Ravine, course N.E.; steep ascent; bears N. & S.
33.00	Leave dense undergrowth; thence scattering timber and heavy grass.
40.00	A point 400 ft. above the Sec. Cor. and set a Basalt Stone, 12 x 10 x 8 ins., 8 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which; A Fir, 14 ins. diam., bears N. 61° E., 81 lks. dist. marked $\frac{1}{4}$ S. 32, B.T. The old $\frac{1}{4}$ Sec. Cor., A Basalt Stone, 14 x 12 x 5 ins., marked and witnessed as described by the Surveyor-General, bears S. 84° W., 1 ch. 44 lks. dist. I destroy all traces of the old Cor.
40.25	Top of rock-ridge-N. 60° E.; descend thru timber and dense undergrowth; bears N. 75° E. and S. 75° W.
42.00	Slope N.
45.00	Descend abruptly; bears N. 60° E. and S. 60° W.
48.25	Ravine, course N. 20° E.; steep ascent, bears N. 10° W & S. 10° E
50.50	Top of rise or point-N.E.; descend.
57.75	Foot
58.00	Rill, 1 lk. wide, runs N. 50° E., ascend steep hill; bears N.E. & S.W.
74.00	Leave dense undergrowth; thence thru scattering timber.
80.00	A point 600 ft. above the $\frac{1}{4}$ Sec. Cor. and set an iron-stone, 20 x 10 x 8 ins., 15 ins. in ground, for Cor. to Secs. 31 & 32 and raise a mound of stone, 2 ft. base $1\frac{1}{2}$ ft. high, N. of Cor. Pits impracticable. The old Cor. of Secs. 31 & 32, as determined by the witness-trees, described by the Surveyor-General, stone missing, bears S. 82° W., 1 ch. 50 lks. dist. I destroy all traces of this old Sec. Cor. Land: mountainous. Soil; gravel and stone; 3rd & 4th rates. Timber; pine, fir and tamarack. Undergrowth: huckleberry, service berry, .pine, fir, tamarack, willow and bunchgrass.