

Chains	<p>x 4 ins., 10 ins. in ground, for closing Cor. of Secs. 30 &amp; 31, marked C.C. on E. face, with 5 grooves on N. and 1 groove on S. faces, from which</p> <p>A pine, 11 ins. diam., bears S. 29°E., 69 lks. dist. marked T.3 N., R.37 E., S. 31,B.T.</p> <p>No tree in limit N.E. and I raise a mound of stone 2 ft. base, 1½ ft. high on W. end of stone ledge E. of Cor.</p> <p>Pits impracticable.</p> <p>Land; gently rolling and mountainous.</p> <p>Soil; swamp muck, black loam, gravel and stone; 1st, 2nd &amp; 4th rates.</p> <p>Heavily timbered with pine, fir, tamarack and spruce, 50.00 chs.</p> <p>Densely overgrown with pine, fir, tamarack, spruce, alder, willow, cascara, ninebark, fern, huckleberry, rosebriar and bunchgrass, 33.00 chs. N. half good pasture.</p> <p>Mountainous, heavily timbered or lands covered with dense undergrowth, 74.00 chs.</p> <p style="text-align: right;">August 26, 1900.</p>
.50	N.1° 42' W., between Secs. 30 & 36. Summit of rocky ridge, bearing N.30° W. and S. 30° E; descend.
1.00	Trail; bears N. 20°W. and S. 20°E., enter dense undergrowth.
22.35	The Cor. of Secs. 25 & 26, re-established by me, August 26, 1900, an ironstone, 10 x 6 x 5 ins. above ground, marked and witnessed as described in the field notes of survey of subdivisions returned to the Surveyor-General.
	Thence I retrace
	N., between Secs. 25 & 30.
22.500	Enter heavy timber; bears N.W. & S.E.
26.00	Thence scattering timber and undergrowth; steep, grassy slope eastward.
32.00	Enter timber and dense undergrowth; bears E. & W.