

Township 3 N., R. 37 E., W.M.

Chains .89	The closing Cor. of Secs. 20 & 21, now established, a Basalt Stone, 12 x 5 x 4 ins. above ground, marked and witnessed as described in the field notes of survey of subdivisions returned to Surveyor-General.
40.05	The point for $\frac{1}{4}$ Sec. Cor., S. Bdy. of Sec. 16, on heavily timbered bottom at base of mountain; after renewed search, fail to find any trace of old Cor. and set an ironstone, 15 x 12 x 8 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which A Fir, 48 ins. diam, bears N. $22\frac{1}{2}^{\circ}$ E., 39 lks. dist., marked $\frac{1}{4}$ S. 16, B.T.
40,44 $\frac{1}{2}$	A point 850 ft. below the closing Sec. Cor. and 50 lks. S. $89^{\circ} 45' W.$ on the temp. $\frac{1}{4}$ Sec. Cor., set in edge of river, where I set an ironstone, 20 x 8 x 6 ins., 15 ins. in the ground, for witness $\frac{1}{4}$ Sec. Cor., N. Bdy. of Sec. 21, marked W.C., $\frac{1}{4}$ on S. face, from which A fir, 24 ins. diam., bears S. $18\frac{1}{2}^{\circ}$ E, 76 lks. dist. marked W.C., $\frac{1}{4}$ S. 21, B.T.
40.90	Left bank of the Umatilla river, 75 lks. wide, flows N. $40^{\circ} W.$, thence across gravel bar.
49.25	High water bank.
51.00	Old stage road; bears N.W. & S.E.
51.75	Enter field; fence bears N. & S.
62.50	Leave field and enter timber; bears N. & S.
80.11	The Cor. of Secs. 15 & 16, whence the closing Cor. of Secs. 21 & 22, 150 ft. above the witness $\frac{1}{4}$ Sec. Cor., bears N. $89^{\circ} 47' E.$, 90 lks. dist. Land; level, rolling & mountainous. Soil; part arable, gravelly, black loam and stone; 1st, 2nd & 4th rates. Heavily timbered with pine, fir, tamarack, cottonwood and ash, 40.90 chs. Undergrowth, pine, fir, tamarack; alder, willow, cottonwood, maple, fern and bunchgrass. Good pasturage. Mountainous, or heavily timbered land, 58.50 chs.

August 22, 1900.