

Chains	<p>Timber; pine, fir and tamarack, Undergrowth; pine, fir, tamarack and bunchgrass. Good pasturage. Mountainous land, 80.75 chs.</p> <p style="text-align: right;">August 29, 1900</p> <p>West, on a blank line, S. Bdy. of Sec. 18; at 38.28 chs. set temp. <math>\frac{1}{4}</math> Sec. Cor., N. Bdy. of Sec. 19; at 40.00 chs. fail to find any trace the old <math>\frac{1}{4}</math> Sec. Cor. described by the Surveyor-General as a Basalt Stone 4 x 8 x 14 ins. Set temp. Cor. and at 80.00 chs. intersect the Cor. of Secs. 13, 18, 19 &amp; 24, before described.</p> <p>Thence I run East, on a true line, S. Bdy. of Sec. 18 Ascending S.W. slope of ridge.</p> <p>25.00 Top of bare point; descend.</p> <p>37.00 Foot; thence along densely overgrown slope S.</p> <p>40.00 The point for <math>\frac{1}{4}</math> Sec. Cor., S. Bdy. Sec. 18 at edge of undergrowth; set an ironstone, 20 x 8 x 4 ins., 10 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on N. face and raise a mound of stone, 2 ft. base, <math>1\frac{1}{2}</math> ft. high, N. of Cor. Pits impracticable.</p> <p>41.72 A point 100 ft. above the Sec. Cor. and set a Basalt Stone 15 x 10 x 4 ins., 10 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., N. Bdy. of Sec. 19, marked <math>\frac{1}{4}</math> on S. face and raise a mound of stone, 2 ft. base, <math>1\frac{1}{2}</math> ft. high, S. of Cor. Pits impracticable.</p> <p>57.00 On summit of ridge- N. 65°W.; descend; hill bears N.E. &amp; S.W.</p> <p>73.25 Enter dense undergrowth.</p> <p>80.00 The Cor. of Secs. 17 &amp; 18, whence the closing of Cor. of Secs. 19 &amp; 20, 300 ft. above the <math>\frac{1}{4}</math> Sec. Cor., bears S. 88° 34' E., 1 ch. 72 lks. dist.</p> <p>Land; rolling and mountainous. Soil; gravelly and stony; 3rd &amp; 4th rate. Timber; widely scattering pine and fir. Dense undergrowth of pine, fir, laurel, willow and bunch-</p>
--------	---