

Township 3 N., R.37 E., W.M.

Chains	26, B.T.
	No other tree accessible and I raise a mound of stone 2 ft. base, 1½ ft. high, W. of Cor. Pits impracticable
50.50	Small spring of pure water.
62.05	Trail on summit of divide between N. Fork of the Umatilla river and Buck Creek, leading from the Summerville Toll road to Pendleton; bears N. 85° W. and S. 85° E. Descend N. slope of mountain.
62.75	Enter timber and dense undergrowth.
67.15	A fir, 28 ins. diam., on line, I mark with 2 notches on N. & S. sides.
72.50	Hill bears N. 10° E; steep slope westward.
75.00	Ascend slightly; slope S. 80° W.
79.75	Top of ridge point, course N. 30° W.; descend.
80.00	A point 300 ft. above the ¼ Sec. Cor. and set a Basalt Stone, 15 x 12 x 5 ins., 10 ins. in ground, for Cor. of Secs. 23, 24, 25 and 26, marked with 2 notches on S. and 1 notch on E. edges, from which, A fir, 6 ins. diam., bears N. 50° E., 5 lks. dist. marked T3N., R37E., S.24, B.T. A fir, 7 ins. diam., bears S. 13¼° W., 26 lks. dist marked T3N, R37E., S.23, B.T. Land; mountainous. Soil; stony, 3rd & 4th rates. Scantily timbered with pine, fir, tamarack and alder. Densely overgrown with alder, maple, willow, fir, pine, tamarack, huckleberry, cherry, rose and piegrass, 17.25 chains. Good bunchgrass pasturage, 62.75 chs. Mountainous land, 80.00 chs.
40.00	N. 89° 56' E., on a random line between Secs. 24 & 25. Set. temp. ¼ Sec. Cor.
80.44	Intersect E. Bdy. of Tp. 3 lks. S. 0° 56' W. of Cor. of Secs. 24 & 25, established by me, July 26, 1900, which is an ironstone 12 x 5 x 3 ins. above ground, marked and witnessed as described in the field notes of re-