

Chains	partially deadened timber; bears N.E. & S.W.
40.03	A point 200 ft. above the Sec. Cor. and set a Basalt Stone, 15 x 10 x 4 ins. 10 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which, A tamarack, 8 ins. diam., bears N.43° E., 57 lks. dist., marked $\frac{1}{4}$ S.26, B.T. A tamarack, 14 ins. diam., bears S.81 $\frac{1}{2}$ °E., 30 lks. dist., marked $\frac{1}{4}$ S. 35, B.T.
41.30	Foot.
42.51	Stream, scattering, 10 lks. wide, runs N.10°E.; ascend steep, grassy hill; bears N.& S.
45.00	Leave timber and undergrowth; bears N.&S.
49.50	Enter timber and dense undergrowth on ridge-point; bears N.E.
55.00	Descend through partially deadened timber and fallen poles hill bears N.E. and S.W.
66.00	Scattering stream, 10 lks. wide, runs N.10° E.; ascend steep, grassy hill; bears N.15° E. and S.15° W.
68.50	Leave timber and undergrowth; bears N. and S.
80.06	A point 500 ft. above the $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs. 26, 27, 34 & 35. Land; mountainous. Soil; gravelly and stony; 3rd & 4th rates. Timber; pine, fir, tamarack, spruce and cottonwood. Undergrowth; pine, fir, tamarack, spruce, alder, willow, cascara, huckleberry, thimbleberry, elder, pinegrass, rosebriar, fern and bunchgrass, Good pasturage. Mountainous land, 80.06 chs.
	N.0°1' W., between Secs. 26 & 27. Along E. slope of grassy, stony point; bears N.35 ° E.
.75	Descend; hill bears E.& W.
1.10	Enter heavy timber and dense undergrowth; N.E.& S.W.
7.50	Hill bears N.E.& S.W.
16.75	Foot; stream, 3 lks. wide, runs N.40° E.; ascend grassy point thru open timber and undergrowth; bears N.10° E.