

Township 3 N., R.37 E., W.M.

Chains	
54.25	Ascend bluffs; bear N.&S.; scattering timber.
57.00	Top of stony point-S.10°E., descend abruptly into Ravine
58.45	Foot; dry bed of stream, 6 lks. wide; course S.10° E., ascend thru heavy timber and dense undergrowth; hill bears N. & S.
60.75	Top of point-N.E.; descend into same Ravine.
63.75	Foot; rill, 2 lks. wide, runs N.60° E.; ascend main hill thru scattering timber and undergrowth; bears N.E. & S. S.W.
70.75	Ravine; course S.
80.08	A point 500 ft. above the $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs. 28, 29, 32 & 33. Land; mountainous, level and rolling. Soil; gravelly and stony; 3rd & 4th rates. Heavily timbered with pine, fir, tamarack and cottonwood 1212030chs. Densely overgrown with pine, fir, tamarack, willow, nine- bark, laurel, pinegrass, fern, alder, thimbleberry & bunchgrass, 28.55 chs. Good pasturage. Mountainous, heavily timbered or densely overgrown land 80.08 chs.
	N.0°3' W., between Secs. 28 & 29. Ascending steep, grassy ridge thru scattering timber & undergrowth; hill bears N.&S.
2.50	Steep slope S.70° E.
7.00	Top of rise on ridge-point-N.70° E., stock trail; bears N. 70° E. and S.70° W.; descend thru timber and dense undergrowth; bears E.&W.
20.50	Bottom of "Gerkins'" gulch; dry bed of stream, 10 lks. wide, course N.70° E.; ascend; hill bears N.60° E. and S.60° W.
26.50	Scattering timber and undergrowth-grassy hillside.
31.50	Point- S.E.; thence steep slope S.80° E.
36.00	Steeper descent; bears N.70° E. and S.70° W.
40.00	A point 50 ft. above the Sec. Cor. and set a Basalt