

## Township 3 N., R.27 E., W.M.

Chains	S.89° 47' E., on a random line between Secs. 21 & 28.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.10	Intersect N.&S. line, 16 lks. N. of the Cor. of Secs. 21, 22, 27 & 28.
	Thence I run, N.89° 40' W., on a true line between Secs. 21 & 28. Ascending steep, bluffy hill thru widely scattering timber and undergrowth; bears N.E. & S.W.
2.75	Up bluffs.
6.00	Steep, grassy ascent above bluffs.
11.50	Point-S.E.; descend across timbered Ravine.
17.00	Ravine, course S.E.; steep ascent, bears N.&S.
23.50	Leave scattering timber.
32.00	Top of rise on S. slope of Graves' Butte.
33.00	Descend; hill bears N.W. & S.E.
40.05	A point 700 ft. above the Sec. Cor. and set a Basalt Stone, 15 x 8 x 8 ins., 10 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which, A pine, 14 ins. diam., bears S.76° W., 1 ch. 60 lks. dist., marked $\frac{1}{4}$ S.28, B.T. A pine, 17 ins. diam., bears N.54° W., 1 ch. 75 lks. dist., marked $\frac{1}{4}$ S.21, B.T.
41.75	Enter timber; bears N.&S.
49.00	Deep, bluffy ravine; course S.10° E., thence over grassy point through more open timber and undergrowth.
55.00	Along steep, bluffy side of gorge S.; heavy timber.
60.00	Stream, 3 lks. wide, in Ravine, runs S.80° E., ascend thru timber and dense undergrowth.
80.10	A point 200 ft. below the $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs. 20, 21, 28 & 29. Land; mountainous. Soil; sandy loam, gravel and stone; 2nd, 3rd & 4th rates. Timber; pine, fir and tamarack. Undergrowth; pine, fir, tamarack, willow, alder, cherry, ninebark, rosebriar, fern, mullen, pinegrass, thimble- berry, huckleberry and bunchgrass.