

Township 3 N., R.37 E., W.M.

## Chains

Good pasturage.

Mountainous land, 80.10 chs.

August 20, 1900.

N.0°3'W., between Secs. 20 &amp; 21.

Descending steep bank of gulch thru timber and undergrowth; bears E.&amp;W.

1.90 Foot; dry bed of stream, 8 lks. wide, course S.80° E.; ascend steep, grassy hill; bears N.70° E. and S.70° W.

2.75 Scattering timber and undergrowth.

13.00 Top of rocky point-S.E.; descend.

19.50 Bottom of Ravine; course S.E., thence over ridge.

28.50 Trail on summit of ridge; bears E.&amp;W.; descend into canyon of Umatilla River thru dense undergrowth; bears E.&amp;W.

34.00 Ravine, course N.30° E.; leave dense undergrowth on grassy point; steep slope N.E.

39.25 Point-N.E.; steep descent through dense undergrowth; hill bears N.70° E. and S.70° W.

40.00 A point 200 ft. above the Sec. Cor. and set a Basalt Stone, 15 x 10 x 5 ins., 10 ins. in the ground, for  $\frac{1}{4}$  Sec. Cor., marked  $\frac{1}{4}$  on W. face, from which,  
A tamarack, 7 ins. diam., bears N.10 $\frac{1}{2}$ ° E., 1 ch. 29 lks. dist., marked  $\frac{1}{4}$  S.21, B.T.  
A fir, 14 ins. diam., bears S.34 $\frac{1}{2}$ ° W., 1 ch. 95 lks. dist., marked  $\frac{1}{4}$  S.20, B.T.

43.00 Point-N.30° E; steep descent; bears N.65° E. and S.65° W.

47.75 Ravine, course N.25° E; thence steep, grassy slope E.; scattering timber and undergrowth.

55.00 Enter dense undergrowth.

56.00 Ravine, course E.; ascend; hill bears N.20° E. and S. 20° W.

57.00 Leave dense undergrowth.

70.50 Top of point-N.40° E.; descend steep side of canyon; thru timber and dense thickets; irregular bearing E. &amp; W.