

Township 3 N., R. 37 E., W.M.

<p>Chains 75.33</p>	<p>A point about level with the $\frac{1}{4}$ Sec. Cor. and intersect S. Bdy. of Secs. 16, 89 lks. N. $89^{\circ} 45'$ E. of the Cor. of Secs. 16 & 17, which is a Basalt Stone, 16 x 12 x 7 ins. on N.W. face of Spur, marked and witnessed as described by the Surveyor-General.</p> <p>At the point of intersection I set a Basalt Stone, 12 x 12 x 5 ins., 8 ins. in the ground, for closing Cor. of Secs. 20 & 21, marked CC on S. face, with 4 grooves on E. and 2 grooves on W. faces, from which,</p> <p>A leaning fir, 34 ins. diam., bears S. 88° E., 1 ch. 42 lks. dist., marked T.3 N., R.37 E., S.21, B.T.</p> <p>A fir, 6 ins. diam., bears S. $24\frac{1}{2}^{\circ}$ W., 43 lks. dist., marked T.3 N., R.37 E., S.20, B.T.</p> <p>Land; mountainous.</p> <p>Soil; sandy loam, gravel & stone; 2nd, 3rd and 4th rates.</p> <p>Timber; pine, fir and tamarack of indifferent quality.</p> <p>Undergrowth; pine, fir, tamarack, ninebark, willow, cherry, chinquapin, alder, thimbleberry and bunchgrass.</p> <p>Good pasturage.</p> <p>Mountainous land, 75.33 chs.</p> <p style="text-align: right;">August 22, 1900.</p>	
	<p>August 10:</p> <p>N. $0^{\circ} 4'$ W., between Secs. 31 & 32.</p> <p>Ascending steep, stony Spur; bears N. 70° W. and S. 70° E.</p> <p>1.25 Top of narrow ridge, S. 70° E., descend steep, densely overgrown hill, through small timber; bears E. & W.</p> <p>10.15 Ravine; N. 25° E., thence hill bears N.W. & S.E.</p> <p>15.85 Foot; rill, 1 lk. wide, runs E.; ascend through scattering timber- steep, grassy hill; bears N.E. & S.W.</p> <p>17.25 Scattering undergrowth-heavy grass.</p> <p>19.50 Grassy point-S.E.; descend across densely overgrown Ravine.</p> <p>22.00 Bottom of Ravine, course S.E.; steep ascent; bears E. & W.</p> <p>24.00 Leave scattering timber & dense undergrowth.</p>	