

Chains	Description
	At the Cor. of Secs. 29, 30, 31 & 32.
	Thence I run,
	S. 89° 44' E., on a random line between Secs. 29 & 32.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.20	Intersect N. & S. line 5 lks. S. of the Cor. of Secs. 28, 29, 32 & 33.
	Thence I run, N. 89°
	N. 89° 46' W., on a true line between Secs. 29 & 32.
	Ascending steep, stony ridge through scattering timber and dense patches of undergrowth; hill bears N. E. & S. W.
11.00	Top of Ridge; stock trail; bears N. E. & S. W.; descend along steep slope of "Gerkins" gulch through timber and dense undergrowth; bears N. 80° E. and S. 80° W.
21.50	Steeper descent through thickets; bears N. & S.
28.25	Bottom of Ravine, course N.; ascend; dense undergrowth.
32.00	Top of point-N.; descend steep, grassy hill through scattering timber and undergrowth; bears N. 10° E. and S. 10° W.
36.00	Bottom of "Gerkins" gulch; dry bed of stream, 5 lks. wide course N. E. (Running water below) Steep ascent; bears N. 20° W. and S. 20° E.
39.98	A fir, 19 ins. diam., on line, I mark with with 2 notches on E. and W. sides.
40.10	A point 400 ft. above the Sec. Cor. and set a Basalt Stone, 15 x 12 x 4 ins., 10 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. 29, face, from which, A fir, 18 ins. diam., bears N. 25° E., 36 lks. dist., marked $\frac{1}{4}$ S. 29, B. T. A fir, 17 ins. diam., bears S. 38° E., 35 lks. dist., marked $\frac{1}{4}$ S. 32, B. T.
40.75	Leave timber and undergrowth on point-S. E.; steep stony slope S. 10° E.
51.00	Top of Ridge-N. 30° E.; descent through timber and dense undergrowth-partially deadened.
52.75	Bottom of Ravine- at bend- N. 20° E.; over low point.