

Township 3 N., R.37 E., W.M.

| | |
|--------|---|
| Chains | N.30° W. and S.30° E.; scattering undergrowth. |
| 81.79 | A point 100 ft. above the $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs. 29,30, 31, & 32. Land; mountainous. Soil: gravelly and stony; 3rd & 4th rates. Timber; pine, fir and tamarack. Undergrowth; pine, fir, tamarack, alder, willow, laurel, cascara, huckleberry, rosebriar, thimbleberry, fern, and bunchgrasses. Good pasturage. Mountainous land, 81.79 chs. |
| | August 26, 1900 |
| | Determine a true meridian by the solar at the Cor. of Secs. 29, 30, 31 & 32, which observation tallies with that of yesterday. Thence I run, N.0°4' W., between Secs. 29 & 30. Along grassy, stony slope W. |
| 1.50 | Descend through partially deadened timber and dense undergrowth; bears N.E. & S.W. |
| 7.00 | Head of Ravine-N.80°W.; thence along westward slope. |
| 11.00 | Leave dense undergrowth; thence scattering timber. |
| 16.40 | Small spring of pure water, 20 lks. E. of line. |
| 21.00 | Stock trail down point N.W.; steep descent through dense undergrowth and thickets; bears E & W. |
| 38.45 | Foot; Ravine, course N.40° W.; scattering timber and undergrowth. |
| 40.00 | A point 400 ft. below the Sec. Cor. and set a Basalt Stone, 15 x 8 x 6 ins., 10 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which, A fir, 22 ins. diam.; bears S.56 $\frac{1}{4}$ ° E., 1 ch.50 lks. dist., marked $\frac{1}{4}$ S.29, B.T. A pine, 28 ins. diam.; bears N.42° W., 3 ch. dist., marked $\frac{1}{4}$ S. 30, B.T. |
| | Thence along steep, grassy slope S.80° W. |
| 46.75 | Descend through dense undergrowth; bears N.E. & S.W. |