

## Township 3 N., R. 37 E., W.M.

Chains	
12.50	Scattering timber and undergrowth.
23.00	Top of point; descend across branch of large Ravine S.
27.25	Ravine, course S.60° E.; ascend steep, grassy hill thru scattering timber and undergrowth; bears N. & S.
40.05	A point 600 ft. above the Sec. Cor. and set an ironstone, 12, 10 x 6 ins., 8 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which, A fir, 11 ins. diam., bears S.55 $\frac{1}{2}$ ° E., 61 lks. dist. marked $\frac{1}{4}$ S.29, B.T. A pine, 36 ins. diam., bears N, 76 $\frac{1}{2}$ ° W., 66 lks. dist. marked $\frac{1}{4}$ S.20, B.T.
49.75	Top of sharp, rocky Divide, between "Bobsled" and S. Fork trail, along summit; bears S.20° E. and S.20° W. descend through timber and dense undergrowth; bears N.E. & S.W.
55.00	Foot; ascend from head of Ravine-N.W.
59.75	Top of point, N.; descend steep, grassy hill through widely scattering timber and undergrowth; bears N. & S.
78.00	Deep Ravine-N.65° W., thence along steep side of Ravine through timber and dense undergrowth.
80.10	A point 500 ft. above the $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs. 19, 20, 29 & 30. Land; mountainous. Soil; gravelly and stony; 3rd & 4th rates. Timber; pine, fir and tamarack. Undergrowth; pine, fir, tamarack, willow, alder, cherry, ninebark, rosebriar, thimbleberry, fern and bunchgrass. Good pasturage. Mountainous land, 80.10 chs.

August 27, 1900

40.00	Determine a true meridian by the solar at the Cor. of Secs. 19, 20, 29 & 30. Thence I run, N.89° 55' W., on a random line between Secs. 19 & 30. Set temp $\frac{1}{4}$ Sec. Cor.
-------	--