

## Township 3 N., R.37 E.,W.M.

Chains	growth; ascend grassy hill; bears NW. & SE.
57.25	Top of point-W.; descend through timber and dense under-growth growth; bears N.65° E. and S.65° W.
62.00	Foot; Ravine, course W.; ascend grassy hill; bears E.&W.
68.50	Top of point-S.W.; thence hill bears N.10° W. and S.10°E.
73.75	Small, densely overgrown Ravine, course S.W.; ascend.
75.16	A point 250 ft. below the $\frac{1}{4}$ Sec. Cor. and intersect S. Bdy. of Sec.17, 1 ch. 72 lks., S.88° 34' E. of the Cor. of Secs. 17 & 18, which is a mound of stone, pits and stake with marked stone, witnessed as described by the Surveyor-General. The stake is badly decayed, therefore I set a Basalt Stone, 15 x 10 x 8 ins., 10 ins in the ground, for Cor. of Secs. 17 & 18, marked with 5 notches on E. and 3 notches on S. edges, from which, the orig- inal witness-tree, a fir, 14 ins. diam., bears E., 70 lks. dist.; the original marks are weather worn and indistinct-which defect I also repair.
	At the point of intersection I set a Basalt Stone, 15 x 10 x 8 10 x 5 ins., 10 ins. in the ground, for closing Cor. of Secs. 19 & 20, marked CC on S. face, with 5 grooves on E. and 1 groove on W. faces; and raise a mound of stone, 2 ft. base, 1 $\frac{1}{2}$ ft. high, S. of Cor. Pits im- practicable.
	Land; mountainous.
	Soil; gravelly and stony; 3rd & 4th rates.
	Timber; pine, fir and tamarack.
	Undergrowth; pine, fir, tamarack, willow, ninebark, alder, rosebrar, cherry, fern, arrowwood and bunchgrasses.
	Good pasturage.
	Mountainous land, 75.16 ch.
	August 29, 1900.
	General Description.
	This South half of Township contains little variety of land other than mountainous and the soil is mostly gra velly loam, of good strength, however, producing a generous