

1.
 South Boundary of Township 4 N., R.38 E.,W.M.
 As surveyed by George S. Pershin, U.S.Deputy Surveyor.
 Under Contract No. 304. Dated Sept. 19, 1878.

Chains.	
	<p>I begin at the Cor. of Tps. 3 & 4 N., Rs.37 & 38 E., and with Burt's Improved Solar Compass, I run East on the S. Bdy. of Sec. 31.</p> <p style="text-align: right;">Var. 20° E.</p>
40.00	<p>Set pine post on S.W. slope for $\frac{1}{4}$ Sec. Cor. A fir, 8 ins. diam., bears N.70° E.,8 lks. distant. A fir, 18 ins. diam.,bears S.5° W.,36 lks. distant.</p>
80.00	<p>Set fir post on nearly level for Cor. to Secs.31,32,5 & 6 +500 A tamarack, 8 ins. diam.,bears N.42° E.,16 lks. dist. A pine, 10ins. diam., bears S.80° E.,18 lks. dist. A pine, 10 in.s diam., bears S.56° W.,12 lks. dist. A tamarack, 10 in.s diam.,bears N.70° W., 18 lks. dist.</p> <p>Land; surface mountainous. Soil; 3rd rate. Timber; heavy pine, tamarack and fir.</p>
	<p>East on the S. Bdy. of Sec. 32</p> <p style="text-align: right;">Var.21°30' E.</p>
40.00	<p>Set pine post on nearly level for $\frac{1}{4}$ Sec. Cor. A pine, 10 ins. diam., bears N. 15 ° E.,12 lks. dist. A pine, 15 ins. diam., bears S.50° W., 13 lks. dist.</p>
73.50	<p>Spring branch, course NE. & S.</p>
80.00	<p>Set fir post on W. face of ridge for Cor. to Sec. 32,33, 4 and 5. A tamarack, 18 in.s diam., bears S.36° E., 32 lks. dist A fir, 8 ins. diam., bears S.48 ° W., 107 lks. dist. A tamarack,22 ins. diam.,bears N.30° W.,58 lks. dist.</p> <p>No tree on N.E. Land; mountainous. Soil; 2nd & 3rd rate. Timber; heavy, pine, fir and tamarack and spruce.</p> <p style="text-align: right;">June 6th, 1879</p>
	<p>East on S. Bdy. of Sec. 33</p> <p style="text-align: right;">Var. 25° 00' E.</p>
7.50	<p>Road to La Grande,N.W. & S.E.</p>
37.50	<p>Spring branch, course N.E.</p>