

South Bdy. Tp.3 N., R.38 E.,W.M.

Chains	S.89° 41' W. on a true line between Secs. 3 & 34. Var. 20° 15' E.
80.00	<p>*****</p> <p>Marked a fir tree, 40 ins. diam., for Cor. to Secs. 3, 4, 33 & 34, on S.W. slope in heavy fir and tamarack timber T.3 N., S.34 on N.E., R.38 E.,S.3 on S.E., T.2 N.,S.4 on S.W., and S.33 on N.W. faces, with 3 notches on E.&W. edges, from which, A fir, 22 ins. diam., brs. S.29° E., 33 lks. dist., marked T.2 N.,R.38 E.,S.3,B.T. A fir, 30 ins. diam., brs. S.71° W., 62 lks. dist., marked T.2 N.,R.38 E.,S.4,B.T. A fir, 40 ins. diam., brs. N. 17° E., 87 lks. dist., marked T.3 N.,R.38 E., S.34,B.T. A fir, 40 ins. diam., brs. N. 72° W., 155 lks. dist., marked T.3 N.,R.38 E.,S.33,B.T.</p> <p>Land; rolling and hilly table land. Soil; gravelly 2nd rate. Timber; fir and tamarack.</p>
15.20	<p>S.89° 41' W. between Secs. 4 & 33. Var. 21° E.</p> <p>Descent gradual thru heavy fir and tamarack timber.</p>
40.00	<p>W. between Secs. 4 & 33.</p> <p>Spring branch, course S.E.. Nearly level thru dead timber.</p> <p>Set post, 3½ ft. long, 3 ins. sq., 18 ins. in the ground, for ¼ Sec. Cor., marked ¼ S. on N.& S. faces in dead timber, from which, A spruce, 15 ins. diam., brs. S.9° W., 59 lks. dist., marked ¼ S.,B.T. A fir, 6 ins. diam., brs. N. 72° W., 37 lks. dist., marked ¼ S.,B.T.</p>
80.00	<p>Var. 21° 30' E.</p> <p>The dead timber on table land, marked a fir tree, 6 ins.</p>