

South Bdv., T. 3 N., R. 38 E., W.M.

Chains

Land; mountainous, sloping W.
Soil; to 65.00 chs., gravelly 4th rate, from 65.00 chs. to Cor., 1st rate.
Timber; fir and tamarack.

Oct. 7, 1881

This line runs over the summit of the Blue Mountains, dividing the waters the head of the Umatilla River N. and Phillips Creek on the South.

It runs thru heavy, dead and fallen timber.

Resurvey of Exterior Lines of T. 3 N., R. 38 E., W.M.
Surveyed by John W. Kimbrell; U.S. Deputy Surveyor
Under Contract No. 700.
Dated Feb. 9th, 1899

West on true line between Secs. 3 & 4.

80.00

Set fir post, 3 ft. long 4 ins. sq., 24 ins. in the ground, for Cor. to Secs. 3, 4, 33 and 34, marked

T3N., S. 34 on N.E.

R38E., S. 3 on S.E.

T2N., S. 4 on S.W. and

S. 33 on N.W. faces, with 3 notches on E. and W. edges, from which,

A fir, 9 ins. diam., brs. N. 88° E., 14 lks. dist., marked T. 3 N., R. 38 E., S. 34, B.T.

A fir, 7 ins. diam., brs. S. 16° E., 24 lks. dist., marked T. 2 N., R. 38 E., S. 3, B.T.

A fir, 6 ins. diam., brs. S. 19° W., 51 lks. dist., marked T. 2 N., R. 38 E., S. 4, B.T.

A fir, 24 ins. diam., brs. N. 44° W., 24 lks. dist., marked T. 3 N., R. 38 E., S. 33, B.T.

From the Cor., the old Sec. Cor., a tree Cor., marked and witnessed as described by the Surveyor-General, brs. S. 34° W., 79 lks. dist. I destroy marks on Cor. and bearing trees.

3434