

Retracement S. Bdy., T.4 N., R.38 E.,W. M.

Chains		Feet
161.50	Intersect W. Bdy.of Tp., 31 lks. S. of established Cor. to Tps. 3 & 4 N.,Rs. 37 & 38 E., which is a post, marked and witnessed, as described by the Surveyor General.	
	Thence I run N.88°46'E. on true line on S. Bdy. Sec. 31.	
39.75	The $\frac{1}{4}$ Sec. Cor., which is a post, marked & witnessed, as described by the Surveyor General.	
	Thence S.89°28' E. on true line	
40.75	The Cor. to Secs. 31 & 32, which is a post, marked & witnessed, as described by the Surveyor General.	
	Land; mountainous. Soil; 3rd rate. Timber; fir, pine & tamarack. Dense undergrowth; willow & alder. Mountainous & heavily timbered land, 80.50 chs.	
	S. 89°20'E. on true line bet. Secs. 6 & 32.	
38.25	The Closing Cor. of Secs. 5 & 6.	
40.25	The $\frac{1}{4}$ Sec. Cor. on S. Bdy. of Sec. 32, a post, marked & witnessed, as described by the Surveyor General.	
	S.89°32'E. on true line bet. Secs. 5 & 32.	
40.75	The Cor. to Secs. 33 & 32.	
	Land; mountainous, rolling & heavily timbered. Soil; 2nd rate. Timber; pine, spruce & tamarack. Dense undergrowth of willow, alder & small growth of pine, & spruce. Mountainous land, 81.00 chs.	
	Sept. 7, 1903.	
	Retracement of 3 Subdivision $\frac{1}{2}$ Miles in T 3 N R 38 E W M. As executed by Otis O. Gould, U.S. Deputy Surveyor, Under Special Instructions, Group 234, Dated July 11th, 1939.	
	"Correction of the Survey executed by John W. Kimbrell, Deputy Surveyor, in 1903."	
	The $\frac{1}{4}$ Sec. Cor. of Secs. 3 and 4, is the rotten remains of old stake, bearing traces of incomplete scribe marks.	
	At point for Cor.	