

Retracement of 3 Subdivision $\frac{1}{2}$ Miles in T 3 N R 38 E W M.

Chains

Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with the marked stake deposited at the base, for $\frac{1}{4}$ Sec. Cor., with brass cap marked

↑
S 4 | S 3
1939

from which

A pine, 14 ins. diam., brs. N.64°E., 78 lks. dist., marks grown over. (Old B.T.)

A pine, 10 ins. diam., brs. N.28°W., 22 lks. dist., marks grown over. (Old B.T.)

Thence

N.0°02'W., on true line bet. Secs. 3 and 4.

Desc. 567 ft. over NE. slope, through heavy timber and dense undergrowth.

29.95 Intersect S. Bdy. of T 4 N R 38 E.

Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, for Closing Cor. of Secs. 3 & 4, with brass cap marked

T4NR38E
S34
S 4 | S 3
T3N | R38E
C C
1939

from which

A spruce, 16 ins. diam., brs. S.89°E., 18 lks. dist., marked T 3 N R 38 E S 3 C C B T. (Old B.T.)

A fir, 16 ins. diam., brs. S.57 $\frac{1}{2}$ °W., 70 lks. dist., marked T 3 N R 38 E S 4 C C B T. (Old B.T.)

From point of intersection the $\frac{1}{4}$ Sec. Cor. of Sec. 34 only, brs. N.89°10'E., 3.45 chs. dist., heretofore described.

30.13 The original Closing Cor. of Secs. 3 and 4, which is a spruce stump, 20 ins. diam., marked with 3 notches on E. and W. sides, and T 3 N R 38 E on S. side.

from which

A spruce, 16 ins. diam., brs. S.45°E., 25 lks. dist., marked T 3 N R 38 E S 3 C C B T. (Old B.T.)

A fir, 16 ins. diam., brs. S.51°W., 83 lks. dist., marked T 3 N R 38 E S 4 C C B T. (old B.T.)

I obliterate the marks on this tree Cor. stump and leave the two bearing trees intact for accessories to the new Closing Cor. of Secs. 3 and 4, heretofore described.

Land; mountainous.

Soil; rocky loam, 3rd rate.