

S. Bdy. T. 3 S., R. 30 E., W. M.

Chains		Feet
	<p>A Pine 43 ins. diam. brs. S. 13° W. 106.  " " 36 " " " N. 10° W. 72.</p> <p>No other trees.</p> <p>Land; Surface, mountainous.</p> <p>Soil; 2nd &amp; 3rd rate and stony.</p> <p>Good Pine &amp; Fir timber in canyon. Good grass; well adapted to grazing.</p>	
	S. along the E. Bdy. of Sec. 25.	
		Var. 22° 45' E
6.00	Dry bed of creek 10 lks. wide course N. W.	
16.00	Leave timber course. S. E. & N. W.	
	Up East side of ridge	
40.00	Set stone 18 x 10 x 5 on E. Side of ridge for $\frac{1}{4}$ Sec. Cor.	+400
58.00	Top of ridge N. W. & S. E.	+250
80.00	Set stone 17 x 8 x 7 on S. E. side of ridge for Cor. to Sec. 25 & 36. Dug pits, drove stake and raised mounds of stone around stone and stake.	-50
	Land; surface mountainous.	
	Soil; 3rd and 2nd. rate and stony; good grass; some pine and Fir timber on the North Chs. Adapted to grazing.	
	S. along the E. Bdy. of Sec. 36.	
		Var. 14° 15' E.
40.00	Set Stone 16 x 10 x 7 on small flat for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone 22 x 12 x 6 in sag near shallow ravine for Cor. to Townships 3 and 4 S. Rs. 30 and 30 $\frac{1}{2}$ E. W. M.	-50
	A Pine 48 in. diam brs. S 60° E. 352 lks. dist.	
	" " 30 " " " S 24° W. 155 lks. dist.	
	No trees on N. side.	
	Built mound of stone at Cor.	
	Land; surface irregular and broken;	
	Soil 3rd & 2nd rate; some pine & Fir timber in canyons near the line; good grass and well adapted to grazing.	
	Oct. 29.	