

S. Bdy. T. 3 S., R. 30 E. W. M.

Chains		Feet
	stake and Cor. Land; surface broken, Soil; 3rd and 2nd rate, good grass House and farm about one mile N.	
S. 89° E. on the S. Bdy of Sec. 33.		
	Var. 19° 30' E	
19.00	Ravine opens N.	-100
40.00	Set stone 15 x 10 x 5 on ridge sloping E. for $\frac{1}{4}$ Sec. Cor.	+150
67.50	Enter timber S. W. and N. E.	
70.50	Brook 5 lks. wide course N. E.	-180
80.00	Set stone 16 x 10 x 8 on N. W. hillside for Cor. to Secs.	+ 50
	33, 34, 3 and 4 from which, A Pine 20' ins. diam. brs. N. 32° E. 8 lks. dist. " " 11' " " " S. 10° W. 34 lks. dist. " " 13' " " " N. 40° W. 9 lks dist.	
	No other trees.	
	Land; surface irregular and broken, Soil 2nd and 3rd rate, Some good Pine, Fir and Tamarack timber, good grass in open ground.	
	Nov. 2, 1878.	
S. 89° 47' E. on the S. Bdy. of Sec. 34.		
	Var. 21° E.	
36.00	Leave timber course S. E. & N. W.	
40.00	Set stone 16 x 10 x 8 on N. W. hillside for $\frac{1}{4}$ Sec. Cor.	+50
	A Pine 12 in. diam. brs. S. 26° W. 155 lks. dist. House and farm N. about a mile	
55.00	Top of ridge N. E. & S. W.	+100
80.00	Set stone 17 x 10 x 8 on S. W. rocky point for Cor. to	+150
	Secs. 34, 35, 2 and 3. A Pine 20 in. diam. brs. S. 34° W. 322 lks. dist. No other trees, raised mound of stone at corner.	
	Land; surface broken and irregular,	