

S. Bdy. T. 3 S., R. 30 E., W. M.

Chains	<u>General Description</u>	Feet
	<p>The S. Eastern and Southern part is mountainous, the central western and northern part, contains a large amount of agricultural land.</p> <p>There is considerable timber in the larger canyons. Pine, Tamarck and Fir. There is excellent bunch grass nearly all over this township.</p> <p>As near as I could learn there are about fifteen bona fide settlers in this township and the larger part with families, and it should be subdivided</p>	
	<p>Resurvey of S. Bdy of T. 3 S., R. 30 E., W. M. By George S. Pershin, U. S. Deputy Surveyor Under Contract No. 332, Dated July 29, 1879.</p>	
	<p>Having discovered a material <u>error</u> in the S. Bdy. of Tp. 3 S. R. 30 E and having run this Bdy myself and there being as yet no Subdivisions connected therewith, and for the purpose of preventing irregularity, and confusion I proceed and resurvey this South Bdy.</p> <p>I begin at the cor. to Tps 3 S. Rs. 30 & 30$\frac{1}{2}$ E. and with Burts Improved Solar compass I run W. on a random line along the S. Bdys. of Secs. 36, 35, 34, 33, 32 & 31 and at 6 miles 3 chs. & 68 lks. to a point 186 lks. S. of the stone the Cor. to Tps 3 & 4 S. Rs. 29 & 30 E. making my correction 31 lks. N per mile. I therefore begin at the Cor. to Tps. 3 & 4 S. and I run,</p> <p>S. 89° 47' E. on a true line along the S. Bdy. of Sec. 31.</p> <p style="text-align: right;">Var. 21° 00' E.</p>	
43.68	Set Basalt stone 12 x 10 x 8 on S. E. face of hill for $\frac{1}{4}$ Sec Cor.	
45.50	Wagon Road N. E. & S. W. to timber	
48.00	Foot of hill & ravine opens N.	-250
65.00	On spur extending N.	+200
83.68	Set basalt stone 20 x 14 x 7 on E. face of spur & marked post in mound of stone for Cor. to Secs. 31, 32, 5 and 6.	
	<p>Land; surface mountainous; Soil; 3rd and 2nd rate, good grass, No timber on line.</p>	