

S. Bdy. T. 3 S., R. 30 E., W. M.

Chains	Note: The excess in the length of this line is caused by the W. Bdy. <u>not being</u> a due N. & S. line but a corrected random line.	Feet
	S. 89° 47' E. on a true line along the S. Bdy. of Sec. 32.	
	Var. 18° 45' E.	
1.50	Shallow gulch course N.	-30
18.00	On spur	+150
36.50	Brook 8 lks. wide course N.	-200
37.00	Wagon Road N. & S. to timber	
40.00	Set Basalt Stone 16 x 8 x 5 on W. face of spur for $\frac{1}{4}$ Sec. Cor.	+30
52.00	On spur extends N.	+130
74.00	In Gulch extends N.	-130
80.00	Set Basalt stone 14 x 10 x 6 and marked post in mound of stone on N. W. side of spur for Cor. to Sec. 32, 33, 4 and 5.	+40
	Land; surface broken & mountainous, Soil 3rd and 2nd rate, good grass	
	S. 89° 47' E. on a true line along the S. Bdy. of Sec. 33,	
	Var. 21° 45' E.	
26.00	On spur extends N.	+100
40.00	Set Basalt stone 16 x 10 x 5 on level plateau for $\frac{1}{4}$ Sec. Cor	+ 60
76.00	Enter timber course N. E. & S. W.	
77.00	Brook 4 Lks. wide course N. E.	-180
80.00	Set Basalt stone 17 x 8 x 6 on N. slope for Cor. to Secs. 33, 34, 3 & 4 from which,	
	A Pine 20 inches diam. Brs. N. 23 E 62 Lks. dist.	
	" " 20 " " " S. 48 E. 90 " "	
	" " 24 " " " S 5° W. 16 " "	
	" " 30 " " " N. 80° W 26 " "	
	Land; surface moutainous,	