

## Subdivisional Lines, T. 3 S., R. 30 E.

Chains		Feet
	Some good timber along brook, Good grass in open land.	
	<hr/>	
	E. on a random line between Sec. 13 and 24, Var. 18° 45' E	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.88	Intersected E. Bdy. 18 Lks. S. of Cor. to Sec. 13 and 24 from which Cor. I run, S. 89° 52' W on a true line Between Sec. 13 and 24, Var. 20° E	
39.94	Set Basalt stone 15 x 10 x 7 in E. edge of creek bottom for $\frac{1}{4}$ Sec. Cor.	
40.25	Butter Creek 15 Lks wide, course N,	-500
44.00	Leave creek bottom	
79.88	The Cor. to Sec. 13, 14, 23, and 24 Land; surface mountainous, Soil; 3rd rate, small part on creek bottom 1st rate. Willow, Alder and other brush on creek. Good grass. Sept. 7, 1879	+400
	<hr/>	
	N. Between Sec. 13 and 14, Var. 18° 45' E	
40.00	Set Basalt stone 16 x 14 x 5 on N. slope for $\frac{1}{4}$ Sec. Cor.	- 50
	Along down E. side of ridge	
30.00	Set Basalt stone 14 x 8 x 5 and post, in mounds of stone on E. side of ridge for Cor. to Sec. 11, 12, 13 and 14. Land; surface very broken by small ravines and spurs, Soil; 3rd rate and stony. Good grass.	
	<hr/>	
	E. on a random line between Sec. 12 and 13.	