

Subdivisional Lines, T. 3 S., R. 30 E.

Chains		Feet
	Var. 21° 50' E	
38.85	Set Basalt stone 14 x 8 x 6 on W. hillside for $\frac{1}{4}$ Sec. Cor.	
53.00	John Gullifords' house brs. N. 47° W. about 35 Chs. dist.	
78.85	The Cor. to Sec. 2, 3, 10 and 11	-100
	Land; surface rolling, Soil; 3rd and 2nd rate, good grass, but very little farming land on Sec. 2.	
	Sept 10, 1879	
N. between Sec. 33 and 34		
	Var. 20° 30' E	
9.00	Leave timber, course N.E and S.W.	
16.00	Cosby Bowman's house brs. N. 64° E.	
35.00	Foot of mountains proper	-100
40.00	Set Basalt stone 12 x 8 x 6 on N. slope for $\frac{1}{4}$ Sec. Cor.	
47.00	Road to timber E. and W.	
80.00	Set Basalt stone 20 x 10 x 5 on S. face of hill for Cor. to Sec. 27, 28, 33 and 34, also set post in mound of stone.	
	Land; surface rolling, Soil; 2nd 1st and 3rd rate, good grass, some pine, Fir, and Tamarack timber, nearly all excellent farming land, good grass.	
E. on a random line between Sec. 27 and 34.		
	Var. 20° 45' E	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.88	Intersected N. and S. line 28 lks. S. of Cor. to Sec. 26, 27, 34 and 35, from which Cor. I run, S. 89° 48' W. on a true line between Sec. 27 and 34,	
	Var. 21° 45' E	
39.94	To middle of brook, course N. I offset E. 30 lks. and,	-100
39.64	Set Basalt stone 18 x 12 x 10 in. mound of stone on E. bank of brook for $\frac{1}{4}$ Sec. Cor	