

Exterior Lines, T.3 S., R.31 E., W. M.

Chains		Feet
	<p>lieu thereof.</p> <p>Land; surface mountainous.</p> <p>Soil; 2nd & 3rd rate.</p> <p>Some good timber, pine, fir & tamarack, good grass.</p>	
	<p>S. on W. Bdy. of Sec. 31.</p> <p style="text-align: right;">Var. 20° E.</p>	
29.00	Enter timber, course E. & W.	+200
30.50	Brook, 6 lks. wide, course W.	
35.00	Leave timber, E. & W.	
40.00	Set stone, 14 x 10 x 6 on open knoll for $\frac{1}{4}$ Sec. Cor.	+100
	A pine, 36 ins. diam., brs. N. 40° E., 151 lks. dist.	
62.00	Enter timber, course N.E. & S.W.	
80.00	Set stone, 18 x 8 x 7, in small open glade, for Cor. to Tps. 3 & 4 S., Rs. 30 $\frac{1}{2}$ & 31 E., W. M.	
	A pine, 24 ins. diam., brs. N. 55° E., 190 lks. dist.	
	A pine, 16 ins. diam., brs. S. 11° E., 283 lks. dist.	
	A pine, 12 ins. diam., brs. S. 17° W., 196 lks. dist.	
	A pine, 28 ins. diam., brs. N. 55° W., 111 lks. dist.	
	Land; surface mountainous.	
	Soil; 3rd rate.	
	Good timber in places, pine, fir & tamarack, good grass.	
	Nov. 5, 1878.	
	<p>I find the post lying at side of mound, the Cor. to Tps. 2 & 3 S., Rs. 31 & 32 E. and from this Cor., I run S. along E. Bdy. of Sec. 1.</p> <p style="text-align: right;">Var. 20° 50' E.</p>	
20.00	Top of ridge, N.W. & S.E.	+300
38.00	Ravine, course W.	-100
40.00	Set stone, 24 x 14 x 12 on N. hillside, for $\frac{1}{4}$ Sec. Cor.	+20
80.00	Set stone, 20 x 12 x 10 on N.E. face of mountain, for Cor. to Secs. 1, 12, 6 & 7; dug pits & raised stone mound around Cor.	
	Land; surface, mountainous.	
	Soil; 3rd & 2nd rate, good grass.	