

Exterior Lines, T.4 S., R.31 E., W. M.

Chains		Feet
80.00	<p>Set basalt stone, 16 x 10 x 5 on small level table land, for Cor. to Secs. 1 & 2.</p> <p>A pine, 32 ins. diam., brs. S.25°E., 92 lks. dist.</p> <p>A pine, 18 ins. diam., brs. S.34°W., 95 lks. dist.</p> <p>Land; surface mountain plateau.</p> <p>Soil; 3rd & 2nd rate.</p> <p>Heavy timber, with open glades, pine, tamarack & fir. Some dense underbrush, young fir & tamarack. Good grass in openings.</p>	
<p>S.89°55' W. on true old line, along N. Bdy. of Sec. 2. Var. 20°00' E.</p>		
19.22	Old ¼ Sec. Cor. in good repair.	
40.00	<p>Set basalt stone, 14 x 12 x 6 on steep S. slope, for ¼ Sec. Cor.</p> <p>A pine, 18 ins. diam., brs. S.25°W., 7 lks. dist.</p>	
59.44	<p>Old Cor. to Secs. 33 & 34, T.3 S., R.31 E.</p> <p>A pine, 48 ins. diam., brs. N.10°E., 80 lks. dist.</p> <p>A pine, 18 ins. diam., brs. N.18°W., 98 lks. dist.</p> <p>A stone, 20 x 10 x 8.</p> <p>Cor. in good condition.</p>	
80.00	<p>Set basalt stone, 16 x 10 x 8, on steep S. slope, for Cor. to Secs. 2 & 3.</p> <p>A pine, 18 ins. diam., brs. S.78°E., 142 lks. dist.</p> <p>A pine, 24 ins. diam., brs. S.42°W., 86 lks. dist.</p> <p>Land; surface mountainous.</p> <p>Soil; 3rd & 2nd rate.</p> <p>Pine, tamarack & fir timber, with open glades.</p> <p>Good grass; a small part, good farming land.</p>	100
<p>S.89°55' W. on old true line, along N. Bdy. of Sec. 3. Var. 18°45' E.</p>		
19.42	Old ¼ Sec. Cor. in good repair.	
40.00	<p>Set basalt stone, 12 x 10 x 8 on steep S. slope, for ¼ Sec. Cor.</p> <p>A pine, 28 ins. diam., brs. S.2°W., 97 lks. dist.</p>	