

Subdivisional Lines, T.3 S., R.31 E., W. M.

Chains		Feet
	<p>S.89°39' W. on true line bet. Secs. 24 & 25. Var. 20°E.</p>	
13.00	Spring branch, course N.	
40.02	<p>Set pine post on level for $\frac{1}{4}$ Sec. Cor., from which, A tamarack, 10 ins. diam., brs. S.32°E., 16 lks. dist. A fir, 7 ins. diam., brs. N.17 lks. dist.</p>	
57.00	Road, N. & S., Pendleton to Camas Prairie.	
80.04	<p>Cor. to Secs. 23, 24, 25 & 26. Land; surface undulating. Soil; 3rd rate. Heavy timber; pine, tamarack & fir, some small open glades.</p>	
	<p>N. bet. Secs. 23 & 24. Var. 25°30'E.</p>	
30.50	Enter small prairie, course E. & W.	
40.00	<p>Set pine post in small prairie on level for $\frac{1}{4}$ Sec. Cor. A pine, 10 ins. diam., brs. N.85°E., 320 lks. dist. No tree near on W. side.</p>	
48.50	Enter timber, E. & W.	
70.00	Bottom of deep canyon opens N.W.	-300
73.00	Leave timber, S.E. & N.W.	
80.00	<p>Set stone, 20 x 10 x 6, in mound of stone, on W. face of and near top of ridge, for Cor. to Secs. 13, 14, 23 & 24 Also set post, 4 ins. sq., 3 ft. long, properly marked in mound of stone in lieu of pits. Land; surface mountainous. Soil; 3rd rate. Heavy timber; pine, tamarack & fir. Good grass in prairie. April 30, 1879.</p>	
	<p>E. on random line bet. Secs. 13 & 24. Var. 25°30'E.</p>	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.96	<p>Intersected E. Bdy., at Cor. to Secs. 13 & 24, from which Cor., I run W. on true line bet. Secs. 13 & 24.</p>	