

## Subdivisional Lines, T.3 S., R.31 E., W. M.

Chains		Feet
80.70	The Cor. to Secs. 3, 4, 9 & 10. Land; surface mountainous. Soil; 3rd & 2nd rate, some timber along creek, pine, fir and cottonwood. Good bunch grass.	+150
	N. on random line bet. Secs. 3 & 4. Var. 20°00'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
78.96	Intersected N. Bdy., 100 lks. W. of stone Cor. to Secs. 3, and 4, from which Cor., I run S.00°46'W. on true line bet. Secs. 3 & 4. Var. 22°30'E.	
31.00	Deep gulch, opens N.E.	-200
38.96	Set basalt stone, 20 x 12 x 8 on N.W. face of ridge, for $\frac{1}{4}$ Sec. Cor.	
78.96	The Cor. to Secs. 3, 4, 9 & 10. Land; surface mountainous. Soil; 3rd rate., small part 2nd rate. Good grass. May 9, 1879.	+400
	N. bet. Secs. 32 & 33. Var. 18°45'E.	
12.50	On summit of plateau, enter prairie.	+250
31.00	Enter timber again.	
40.00	Set fir post, on N.W. descent for $\frac{1}{4}$ Sec. Cor. A tamarack, 10 ins. diam., brs. N.85°E., 17 lks. dist. A " 8 " " " S.58°W., 30 " " along W. descent.	
80.00	Set granite stone, 16 x 10 x 6, on W. slope, for Cor. to Secs. 28, 29, 32 & 33, from which, A tamarack, 4 ins. diam., brs. N.58°E., 24 lks. dist. A " 18 " " " S.30°E., 55 " " A " 3 " " " S.28°W., 25 " " A " 18 " " " N.48°W., 59 " "	
	Land; surface mountainous. Soil; 3rd & 2nd rate. Groves of good timber with open glades, pine, tamarack & fir.	