

Subdivisional Lines, T.3 S., R.31 E., W. M.

Chains		Feet
60.50	Leave timber, course E. & W.	
80.00	Set basalt stone, 18 x 14 x 7, on S.W. face of mountain, for Cor. to Secs. 17, 18, 19 & 20. Drove stake & raised mound of stone, around stone & stake in lieu of pits. Land; surface mountainous. Soil; 3rd & 2nd rate. Good timber; pine, fir & tamarack. Good grass in openings.	
<hr/>		
	E. on random line bet. Secs. 17 & 20. Var. 25°15'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.40	Intersected N. & S. line, 64 lks. S. of Cor. to Secs. 16, 17, 20 & 21, from which Cor., I run S. 89°33'W. on true line bet. Secs. 17 & 20. Var. 22°00'E.	
4.00	Brook, 5 lks. wide, course N.W. & enter timber.	60
15.00	Leave timber, N.W. & S.E.	
25.50	Road to sawmill, course N.W. & S.E.	200
39.70	Set pine post, 4 ins. diam., 4 ft. long, on S. slope, for $\frac{1}{4}$ Sec. Cor. Raised mound of stone around post in lieu of pits.	
79.40	The Cor. to Secs. 17, 18, 19 & 20. Land; surface mountainous. Soil; 3rd & 2nd rate. Some heavy timber. Good grass in open ground. Timber; pine, fir & tamarack.	
<hr/>		
	W. on random line bet. Secs. 18 & 19. Var. 25°15'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.82	Intersected W. Bdy., 74 lks. N. of stone Cor. to Secs. 18 & 19, from which Cor., I run N. 89°28'E. on true line bet. Secs. 18 & 19. Var. 21°00'E.	
39.82	Set basalt stone, 15 x 11 x 5, on S. face of ridge, near	