

Subdivisional Lines, T.3 S., R.31 E., W. M.

Chains		Feet
	ravine, opening westward, for $\frac{1}{4}$ Sec. Cor.	
79.82	The Cor. to Secs. 17, 18, 19 & 20. Land; surface mountainous. Soil; 3rd & 2nd rate. Good bunch grass, good for grazing.	+300
<hr/>		
	N. bet. Secs. 17 & 18. Var. 25°15'E.	
22.00	Road to timber & sawmill, course N.W. & S.E.	+250
40.00	Set basalt stone, 15 x 12 x 7, on W. side of spur, extending N., for $\frac{1}{4}$ Sec. Cor.	-250
69.50	Spring branch, course N.W.	-250
80.00	Set basalt stone, 18 x 14 x 6, on W. face of spur, for Cor. to Secs. 7, 8, 17 & 18. Drove stake & raised mounds of stone around stone & stake, in lieu of pits. Land; surface mountainous. Soil; 3rd & 2nd rate. Good bunch grass, well adapted to grazing.	
<hr/>		
	E. on random line bet. Secs. 8 & 17. Var. 22°30'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.82	Intersected N. & S. line, 34 lks. S. of Cor. to Secs. 8, 9, 16 & 17, from which Cor., I run S. 89°45'W. on true line bet. Secs. 8 & 17. Var. 22°30'E.	
1.50	Brook, 6 lks. wide, course N.W.	- 20
2.50	Road to timber, course N.W. & S.E. A cabin brs. N., 150 lks. dist.	
24.00	On spur, extending N.	+350
39.00	Brook, 10 lks. wide, course N.	-300
39.91	Set basalt stone, 16 x 10 x 4, for $\frac{1}{4}$ Sec. Cor.	
66.00	On spur, ex-tending N.	+400
79.82	The Cor. to Secs. 7, 8, 17 & 18. Land; surface mountainous. Soil; 3rd & 2nd rate. Good bunch grass, adaptable for grazing. May 17, 1879.	-200