

Subdivisional Lines of T. 3 S., R. 32 E.

Chains		Feet
	Var. 20° 30' E.	
	Steep descent,	
16.00	A brook 6 lks. wide, course, N.E.	
36.75	Same, 6 lks. wide, course N.W.	
	Descent about 200 ft.	
40.00	Set a basalt stone 12 x 8 x 7 ins. 8 ins. in ground on W. slope for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ on W. Face. A Fir 14 ins. diam. brs. S. 40° E. 37 lks. dist. Marked $\frac{1}{4}$ S. B.T. A Pine 7 ins. diam. brs. N. 38° W. 7 lks. dist. Marked $\frac{1}{4}$ S. B.T.	
	Along W. slope of hill,	
64.58	Intersected N. Bdy. 29, Chs. and 88 lks. W. of Cor. to Secs 34 and 35. T. 2 S. R. 32 E. Set a basalt stone 18 x 10 x 8 on W. slope at intersection, 12 ins. in ground for Cor. to Sec. 1 and 2, marked with 6 notches on S. and 1 notch on E. edges. A Pine 11 ins. diam. brs. S. 86° W. 78 lks. dist. Marked, T. 3 S. R. 32 E., S 2 C.C.B.T. No tree S.E., raised mound of stone along side in lieu of pits. Land; surface, very broken, Soil; 3rd. rate, heavily timbered with Pine, Tamarack and Fir timber, and under growth the Same, with some open glades.	
	May 17, 1882.	
	From the Cor. to Sec. 34 and 35 which is a post marked with 2 notches on E. T. 3 S., R. 32 E., S. 35 on N.E. T. 4 S., R. 32 E. S. 2 on S.E. T 4 S., R. 32 E. S.E. S.E. on S.W. and T. 3 S., R. 32 E. S. 34 on N.W. A Pine 4 ins. diam. brs. N. 28° E. 30 lks. dist. Marked T. 3 S., R. 32 E. S. 35 B.T. A Pine 4 ins. diam. brs. S. 54° E. 12 lks. dist. Marked T. 4 S., R. 32 E. S. 2 B.T.	