

N. Bdy., T.4 S., R.33 E., W. M.

Chains		Feet
28.50	S.89°50'E. on true line on N. Bdy. Sec. 5. Var.21°00'E. Wagon road to Hot Sulphur Springs from settlements & Pendleton, course N.W. & S.E.	
40.00	A pine, 10 ins. diam., on level for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. side, from which, A pine, 8 ins. diam., brs. N.3°W., 25 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 12 ins. diam., brs. S.68°E., 18 lks. dist., marked $\frac{1}{4}$ S., B.T.	
80.00	A fir, 8 ins. diam., on level for Cor. to Secs. 4, 5, 32 & 33, marked T.3 S., R.33 E., S.33 on N.E. T.4 S., R.33 E., S.34 on S.E. T.4 S., R.33 E., S.5 on S.W. T.3 S., R.33 E., S.32 on N.W. and 4 notches on E. & W. sides, from which, A pine, 8 ins. diam., brs. N.14°E., 33 lks. dist., marked T.3 S., R.33 E., S.33, B.T. A pine, 10 ins. diam., brs. S.44°E., 15 lks. dist., marked T.4 S., R.33 E., S.4, B.T. A fir, 8 ins. diam., brs. S.54°W., 14 lks. dist., marked T.4 S., R.33 E., S.5, B.T. A fir, 10 ins. diam., brs. N.58°W., 56 lks. dist., marked T.3 S., R.33 E., S.32, B.T.	
Land; surface rolling. Soil; 2nd & 3rd rate. Heavy pine, tamarack & fir timber, with open glades. Some dense thickets of young timber.		
40.00	S.89°50'E. on true line on N. Bdy. of Sec. 4. Slightly descending. Var.19°00'E. Set basalt stone, 16 x 10 x 8 ins., 11 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. A pine, 8 ins. diam., brs. N.64°E., 44 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 18 ins. diam., brs. S.72°E., 21 lks. dist., marked $\frac{1}{4}$ S., B.T.	