

## Subdivisional Lines, T.3 S., R.33 E., W. M.

Chains	
	N. bet. Secs. 17 & 18. Var. 21°E.
15.00	Descend hill, brs. N.W. & S.E.
40.00	Set pest, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A fir, 8 ins. diam., brs. N.47°E., 9 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 24 ins. diam., brs. S.50°W., 7 lks. dist., marked $\frac{1}{4}$ S., B.T. 500 ft. below Sec. Cor.
50.50	Brook, 2 lks. wide, in ravine, course E., 300 ft. below $\frac{1}{4}$
50.50	Sec. Cor.
60.70	Creek, 10 lks. wide, in canyon, course E., 400 ft. below $\frac{1}{4}$ Sec. Cor. Ascend hill from creek.
80.00	Set basalt stone, 16 x 8 x 5 ins., 12 ins. in ground, for Cor. to Secs. 7, 8, 17 & 18, marked with 4 notches on S. and 2 notches on E. edges, from which, A pine, 40 ins. diam., brs. N.37°E., 31 lks. dist., marked T.3 S., S.8, B.T. A fir, 15 ins. diam., brs. N.15°W., 24 lks. dist., marked R.33 E., S.7, B.T. A fir, 10 ins. diam., brs. S.17°W., 60 lks. dist., marked A.18, B.T. A fir, 8 ins. diam., brs. S.68°E., 26 lks. dist., marked S.17, B.T. 700 ft. above creek. Land; mountainous. Soil; 2nd & 3rd rate. Heavily timbered with pine, fir & tamarack. Dense pine, fir & willow undergrowth.
	E. on random line bet. Secs. 8 & 17. Var. 19°30'E.
	Along hillside, slopes S.
3.00	Descend.