

Subdivisional Lines, T.3 S.,R.33 E.,W. M.

Chains

A pine, 7 ins. diam.,brs. N.42°E., 19,lks. dist.,
marked T.3 S.,S.5,B.T.

A pine, 48 ins. diam.,brs. N.28°W., 42 lks. dist.,
marked R.33 E.,S.6,B.T.

A pine, 30 ins. diam.,brs. S.55°W., 21 lks. dist.,
marked S.7,B.T.

A pine, 20 ins. diam.,brs. S.30°E., 20 lks. dist.,
marked S.8,B.T.

300 ft. above brook.

Land; mountainous.

Soil; 2nd & 3rd rate.

Heavily timbered with pine, fir & tamarack.

E. on random line bet. Secs. 5 & 8.

Along hillside. Var.19°30'E.

3.20 Brook, 2 lks. wide, runs S.

28.80 Brook, 2 lks. wide, runs S.

40.00 Set temp. 1/4 Sec. Cor.

55.00 Top of ridge, slope S.E., 500 ft. high. Descend.

79.90 Intersect N. & S. line, 24 lks. N. of Cor. to Secs. 4, 5,
8 & 9.

Thence I run

N.89°50' W. on true line bet. Secs. 5 & 8.

39.95 Set post, 3 ft. long, 3 ins.sq., 24 ins. in ground,for 1/4
Sec. Cor., marked 1/4 S. on N. face, from which,

A fir, 10 ins. diam.,brs. S.28°W., 7 lks. dist.,
marked 1/4 S.,B.T.

A fir, 16 ins. diam.,brs. N.11°W., 41 lks. dist.,
marked 1/4 S.,B.T.

79.90 The Cor. to Secs. 5, 6, 7 & 8.

Land; mountainous.

Soil; 2nd & 3rd rate.

Heavily timbered with pine, fir & tamarack.

Undergrowth; pine, fir & tamarack.