

Subdivisional Lines, T.3 S., R.33 E., W. M.

Chains	
	W. on random line bet. Secs. 6 & 7. Descend ridge. Var. 19°30'E.
7.75	Brook, 5 lks. wide, in canyon, course S.E. Ascend.
25.00	Top of ridge, brs. N.E. & S.W. & gradually descend 600 ft. above brook.
39.50	Road brs. N. & S.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
69.00	Small ravine, course N.W.
78.00	Intersect W. Bdy. of Tp., 25 lks. S. of Cor. to Secs. 6, 7, 1 & 12, which is a basalt stone, 20 c 18 c 4 ins., marked with 5 notches on S. & 1 notch on N. edges, with mound of stone alongside, from which, A pine, 22 ins. diam., brs. S.78°E., 70 lks. dist., marked T.3 S., R.33 E., S.7, B.T. A fir, 10 ins. diam., brs. S.50°W., 132 lks. dist., marked T.3 S., R.32 E., S.12, B.T. A fir, 10 ins. diam., brs. N.76°W., 121 lks. dist., marked T.3 S., R.32 E., S.1, B.T.
	Thence I run S.89°49'E. on true line bet. Secs. 6 & 7.
38.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A fir, 5 ins. diam., brs. S.2°W., 22 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 8 ins. diam., brs. N.10°W., 19 lks. dist., marked $\frac{1}{4}$ S., B.T.
78.00	The Cor. to Secs. 5, 6, 7 & 8. Land; mountainous. Soil; 2nd rate. Heavily timbered with pine, fir & tamarack. Undergrowth: pine & fir.
	N. on true line bet. Secs. 5 & 6. Var. 19°30'E.
	Ascend hill from Cor.
35.00	Leave timber, brs. E. & W.