

## Dependent Resurvey of East Bdy. of T. 4 N., R. 27 E.

## Chains

- 2.00 House, bears W., about 2.00 chs. dist.  
 4.60 Barn, bears W., about 1.50 chs. dist.  
 18.15 Irrigation ditch, 8 lks. wide, course W.  
 24.50 House, bears E., about 3.00 chs. dist.  
 40.05 The  $\frac{1}{4}$  sec. cor., which is a basalt stone, 12x12x10 ins., set under surface of road, and marked  $\frac{1}{4}$ .

At point for corner

Set an iron post, 3 ft. long, 1 in. diam., 48 ins. in the ground, 1 ft. under surface of road, with the marked stone deposited at the base, for  $\frac{1}{4}$  sec. cor., with brass cap marked

$$\begin{array}{c} \frac{1}{4} \\ \text{S12} \mid \text{S7} \\ 1941 \end{array}$$

At a point 25 lks. W. of true cor. . .

Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with broken glass deposited at the base, for witness cor. to the  $\frac{1}{4}$  sec. cor., with brass cap marked

$$\begin{array}{c} \frac{1}{4} \\ \text{S12} \mid \text{S7} \\ 1941 \end{array} \begin{array}{l} \text{WC} \\ 25 \\ \text{W} \end{array}$$

Thence with new measurement.

- 17.20 House, bears E., about 1.50 chs. dist.  
 17.60 Irrigation ditch, 25 lks. wide, course S.70°W.  
 24.00 Road, turns to NE.; thence in sagebrush.  
 40.05 The cor. of secs. 1, 6, 7, and 12, which is a basalt stone, 18x11x10 ins., firmly set, marked with 1 groove on N. and 5 grooves on S. face.

At point for cor.

Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, with marked stone deposited at the base, for cor. of secs. 1, 6, 7, and 12, with brass cap marked

$$\begin{array}{c} \text{T4N} \\ \text{R27E} \mid \text{R28E} \\ \text{S 1} \mid \text{S 6} \\ \text{S12} \mid \text{S 7} \\ 1941 \end{array}$$

dig pits, 18x18x12 ins., in each sec., 3 ft. dist.

Land, rolling.

Soil, sandy, 2nd rate.

No timber; undergrowth, sagebrush and greasewood.

N.0°45'E., bet. secs. 1 and 6.

Over rolling land, through scattering sagebrush.