

Dependent Resurvey of East Bdy. of T. 4 N., R. 27 E.

Chains

40.57 Proportionate measurement.

Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with broken glass deposited at the base, for $\frac{1}{4}$ sec. cor., with brass cap marked

$$\begin{array}{c} \frac{1}{4} \\ S \ 1 \ | \ S \ 6 \\ 1941 \end{array}$$

dig pits, 18x18x12 ins., N. and S. of post, 3 ft. dist.

81.68 The closing cor. of Tps. 4 N., Rs. 27 and 28 E., previously described.

Land, rolling.

Soil, sandy, 2nd rate.

No timber; undergrowth, sagebrush and greasewood.

Dependent Resurvey of East Bdy. of T. 3 N., R. 27 E.
by Otis O. Gould, Surveyor, under special
instructions dated Jan. 26, 1938

N.0°05'E., bet. secs. 1 and 6.

80.60 The locally recognized and accepted point for cor. of Tps. 3 and 4 N., Rs. 27 and 28 E., which has been perpetuated with a basalt stone, 18x16x10 ins., deposited 26 ins. under surface of road, marked x.

At a point 28 lks. E. of true cor.

Set an iron post, 3 ft. long, 3 ins. diam., 27 ins. in the ground, with broken glass deposited at the base, for witness cor. to the cor. of Tps. 3 and 4 N., Rs. 27 and 28 E., with brass cap marked

$$\begin{array}{c} T4N \\ R27E \ | \ R28E \\ S36 \ | \ S31 \\ WC \ \frac{S \ 1 \ | \ S \ 6}{T3N} \\ 1940 \end{array}$$