

Resurvey of the Exterior Bdys. of T. 4 N., R. 27 E., W.M.

Chains		Feet
	<p>etc., as per instructions, for Cor. to Secs. 12 & 13.</p> <p>Drove Willow stake, 2 ft. long, 2 ins. sq., in E. pit.</p> <p>Land; gently rolling</p> <p>Soil; 2nd rate.</p>	
	<p>N. on E. Bdy. of Sec. 12</p> <p style="text-align: right;">Var. 20° 45' E.</p>	
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	<p>Drove charred stake and raised mound of earth, with pits etc., as per instructions, for Cor. to Secs. 1 and 12.</p> <p>Drove Alder stake, 2 ft. long, 2 ins. sq., in E. pit.</p> <p>Land; gently rolling</p> <p>Soil; 2nd rate.</p>	
	<p>N. on E. Bdy. of Sec. 1</p> <p style="text-align: right;">Var. 21° 00' E.</p>	
40.00	Drove charred stake and raised mound of earth, with pits etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.54	<p>Intersect, 1st standard Parallel, N. 938 lks. W. of the Standard Cor. to Tp. 5-N. Rgs. 27 & 28 E., where</p> <p>Drove charred stake and raised mound of earth, with pits etc., as per instructions, for Closing Cor., to Tp. 4 N., Rgs. 27 & 28 E.</p> <p>Drove Willow stake, 2 ft. long, 2 ins. sq., in E. pit.</p> <p>Land; gently rolling</p> <p>Soil; 2nd rate.</p> <p style="text-align: right;">December 2, 1874.</p>	
	<p>1st Standard Parallel N., R. 27 E., W.M.</p> <p>As surveyed by H.J. G. Maxon and Jard S. Hurd, U.S. Dept. Sur.</p> <p>Under Contract No. 50,</p> <p>Dated February 2, 1860.</p>	
	<p>From the Cor. to Tp. 5 N., Rgs. 27 & 28 E., I run,</p> <p>W. on S. Bdy. of Sec. 36.</p> <p style="text-align: right;">Var. 18° E.</p>	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, trench and	