

Subdivisional Lines of T. 4 N., R. 27 E., W.M.

Chains		Feet
80.00	Intersect N. & S. line, 15 lks. S. of Cor. S. 89° 54' W. on true line	
40.00	Drove charred stake, and raised mound of earth with pits etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	The Cor. Land; gently rolling Soil; 2nd rate.	
N. bet. Sec. 3 & 4		
Var. 21° 15' E.		
40.00	Drove charred stake, and raised mound of earth with pits etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.	
82.20	Intersect 1st Standard Parallel, 10.20 lks. W. of the Standard Cor. to Secs. 33 & 34, where:- Drove charred stake, and raised mound of earth with pits etc., as per instructions, for Closing Cor. to Secs. 3 & 4. Drove Willow stake, 2 ft. long, 2 ins. sq., in E. pit. Land; gently rolling Soil; 2nd rate.	
General Description		
The surface of this tp. is level, or gently rolling. The soil consists generally of loamy sand. The grass in the Eastern tier of Secs. is short and thin but increases gradually, toward the W. The Tp. is adapted to stock raising, being convenient to the Columbia River on the N. and to the Umatilla river on the E. This Tp. has no water courses, and no timber, being on what is known as Umatilla flat.		