

Remeasurements of N. Bdy. of T. 4 N., R. 28 E., W.M.

Chains		Feet
	W. on N. Bdy. of Sec. 4	
		Var. 20° E.
	Descend from post	
26.20	The Stand. $\frac{1}{4}$ Sec. Cor., for Sec. 33	
30.00	Unatilla River, 150 lks. wide, runs N NE. . .	
40.00	Set post for C. $\frac{1}{4}$ Sec. Cor. in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
66.20	Stand. Cor. for Secs. 32 and 33	
80.00	Set post for C. Cor. to Secs. 4 & 5, in mound with trench and pits, and deposited 1 pint of charcoal, as per in- structions.	
	Soil; 3rd rate.	
	Land; rolling	
	Undergrowth Sagewood.	
<hr/> W. on the N. Bdy. of Sec. 5		
		Var. 20° E.
26.20	Stand. $\frac{1}{4}$ Sec. Cor., for Sec. 32	
40.00	Set post for C. $\frac{1}{4}$ Sec. Cor., in mound with trench and pits, and deposited 1 pint of charcoal as per instructions.	
66.20	Stand. Cor. for Secs. 31 and 32	
80.00	Set post for C. Cor. to Secs. 5 & 6, in mound with trench and pit and deposited 1 pint charcoal as per instructions.	
	Land; 3rd rate, rolling	
	Greasewood and Sage Wood.	
<hr/> W. on N. Bdy. of Sec. 6		
		Var. 20° E.
26.20	Stand. $\frac{1}{4}$ Sec. Cor. for Sec. 31	
40.00	Set post for C. $\frac{1}{4}$ Sec. Cor. in mound with trench and pit, and deposited 1 pint of charcoal, as per instructions.	
66.20	The Stand. Cor., for T. 5 N., R. 27 & 28 E.,	
76.20	The C. Cor. for Tp. 4 N., R. 27 and 28 E. Var. 20 E.	
	Soil; 3rd rate.	
	Land; rolling	