

28.                      W.                      S.

T. 4 N., R. ~~29~~-E., W.M. ( E. Bdy.)

Chains		Feet
40.00	Set a post for $\frac{1}{4}$ Sec. Cor., drove a chard stake and raised mound of earth, with trench and pits as per instructions.	
80.00	Set a post for Cor. to Secs. 13, 18, 19 & 24, drove chard stake, raised mound with trench and pits, as per instructions.	
	Land; level, sandy prairie Producing considerable grass on which large bands of cattle were grazing at time of survey. Soil; 2nd and 3rd rate.	
	N. bet. Secs. 13 & 18	Var. 20° 20' E.
40.00	Set a post for $\frac{1}{4}$ Sec. Cor., drove a chard stake and raised mound of earth with trench and pits as per instructions.	
80.00	Set a post for Cor. to Secs. 7, 12, 13, & 18, drove chard stake and raised a mound of earth with trench and pits as per instructions.	
	Land; level, sandy prairie Soil; same as last mile	
	N. bet. Secs. 7 & 12	Var. 20° 20' E
13.00	Commence gentle descent	
40.00	Set a post for $\frac{1}{4}$ Sec. Cor., drove chard stake and raised mound with trench pits, as per instructions.	
62.00	To foot of descent	
80.00	Set a post for Cor. to Secs. 1 & 6, 7 and 12, drove a chard stake, raised mound with trench, pits, as per instructions.	
	Land; rolling prairie Soil; 2nd rate.	
	N. bet. Secs. 1 and 6	Var. 20° E.
40.00	Set a post for $\frac{1}{4}$ Sec. Cor., in mound of earth with trench, pits, as per instructions.	
83.45	Intersect 1st Standard Parallel N., 13.80 chs. W. of standard Cor., drove chard stake and raised mound of earth for C. Cor. to Tp. 4 N., Rgs. <del>27 &amp; 28</del> E., With trench & pits as per instructions.	
	Land; sage, Plain soil, 3rd rate.	