

Subdivisional Lines of T. 4 N., R. 28 E., W.M.  
 As surveyed by Ebenezer E. Haft, U. S. Deputy Surveyor  
 Under Contract No. 93,  
 Dated September 11, 1860

Chains		Feet
	<p>From the Cor. to Secs. 1, 2, 35 &amp; 36, which is the S.W.            Cor. of Laughlins Claim, I run            N. bet. Secs. 35 and 36</p>	
22.75	Neighborhood road up Umatilla, brs. E. SE.	
30.00	Laughlins house brs. N. 85° E.	
38.25	Enter field, course of fence E. and W.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits, and drove charred stakes as per instructions. Laughlin's house brs. S. 70° E.	
66.80	Enter field, fence brs. E. and W.	
77.50	Enter timber, on the Umatilla	
79.00	Intersect the left bank of the Umatilla river, knowing that the Cor. to Secs. 35, 36, 25 and 26, would fall in the river. I set a post as instruction for witness Cor., from which A Balm, 6 ins. diam. brs. N. 82 $\frac{1}{2}$ ° W., 20 lks. dist. " " 10 " " " S. 10° E., 41 lks. dist.	
	Land; level	
	Soil; 1st rate	
	Has timber Balm Maple etc.	
	E. on a random line bet. Secs. 25 & 36 Var. 20° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.60	Intersect E. Bdy. of T., 70 lks. N. of the Cor. to Secs. 25, 26, 30 and 31, from which Cor. I run S. 89° 30' W. on true line bet. Secs. 25 & 36	
17.00	Leave prairie and enter timber.	
22.00	Leave timber and enter prairie Bearing N.	
40.30	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
59.00	Leave prairie, and enter timber	
67.00	Intersect right bank of Umatilla, the line following the river, I offset N., 50 lks. to leave river.	
80.60	To a point on right bank from which witness cor. to secs.	