

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
	Land; gently rolling.	
	<hr/> E. on random line bet. Secs. 13 & 24 Var. 19° 56' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.88	Intersect N. and S. line, 77 lks. N. of the Cor. to Secs. 13, 24, 19 & 18, from which Cor. I run N. 89° 27' W., on true line bet. Secs. 13 & 24	
40.44	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited a pint charcoal as per instructions.	
80.88	The Cor. to Secs. 13, 14, 23 & 24. Soil; 3rd rate, producing grass. Land; gently rolling.	
	<hr/> N. bet. Secs. 13 & 14	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 11, 12, 13 & 14, in mound with trench and pits and deposited 1 pint of charcoal as per instructions. Soil; 3rd rate, producing grass. Land; gently rolling.	
	<hr/> E. on random line bet. Secs. 12 and 13 Var. 19° 40' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.80	Intersect E. Bdy. of Tp., 83 lks. N. of the Cor. to Secs. 13, 12, 17 & 18, from which Cor. I run N. 89° 24' W. on true line bet. Secs. 12 & 13	
40.40	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
80.80	The Cor. to Secs. 11, 12, 13 & 14 Soil; 2nd and 3rd rate. producing some grass. Land; gently rolling	
	<hr/> N. bet. Secs. 11 and 12	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.00	Set post for Cor., to Secs. 11, 12, 1 & 2, in mound with trench and pits and deposited 1 pint of charcoal, as	