

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains	Feet
	*
	October 21, 1860.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.
80.00	Set post for Cor. to Sec. 14, 15, 10 & 11, in mound with trench, and pits and deposited 1 pint charcoal, as per instructions.
	Soil; 3rd rate and sandy Land; rolling
	<hr/>
	E. on random line bet. Secs. 11 and 14 Var. 20° 5' E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.95	Intersect N. and S. line, 63 lks. N. of the Cor. to Secs. 11, 12, 13 & 14, from which Cor. I run N. 89° 33' W. on true line bet. Secs. 11 and 14
39.97 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor. in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.
68.30	Road from Umatilla to Columbia, brs. N.W.
79.95	The Cor. to Secs. 10, 11, 14 & 15. Soil; 3rd rate and sandy Land; rolling
	<hr/>
	N. bet. Secs. 10 & 11
6.00	Road from Umatilla to Columbia, brs. N.W.
40.00	Set post for $\frac{1}{4}$ sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.
80.00	Set post for Cor. to Secs. 2 & 3, 10 and 11, in mound, with trench and pits, and deposited 1 pint of charcoal, as per instructions.
	Soil; 3rd rate, sandy, producing grass. Land; gently rolling.
	<hr/>
	E. on random line bet. Secs. 2 & 11 Var. 20° E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect N. and S. line, 68 lks. N. of the Cor. to Secs. 1, 2, 11 & 12, from which Cor. I run N. 89° 31' W. on true line bet. Secs. 2 & 11
40.05	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint charcoal, as per instructions.
80.10	The Cor. to Secs. 1, 2, 11 & 12