

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
79.70	The Cor. to Secs. 15, 16, 21 & 22 Soil; 3rd rate. Land; rolling	
	N. bet. Secs. 15 & 16	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 15, 16, 9 & 10, in mound with trench and pits and deposited 1 pint charcoal, as per instructions. Soil; 3rd rate, producing grass. Land; rolling	Oct. 22, 1860
	E. on a random line bet. Secs. 10 & 15 Var. 19° 50' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.40	Intersect N. and S. line, 75 lks. N. of the Cor. to Secs. 10, 11, 14 & 15, from which Cor. I run N. 89° 29' W. on true line bet. Secs. 10 & 15	
39.70	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint charcoal as per instructions.	
79.40	The Cor. to Secs. 9, 10, 15 & 16 Soil; 3rd rate. Land; rolling	Oct. 23, 1860
	N. bet. Secs. 9 & 10	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 3, 4, 9 & 10, in mound with trench and pits, and deposited 1 pint of charcoal as per instructions. Soil; 3rd rate. Land; level; grease and sage wood.	
	E. on random line bet. Secs. 3 & 10 Var. 20° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.52	Intersect N. and S. line, 80 lks. N. of the Cor. to Secs. 3, 4, 9 & 10, from which Cor. I run N. 89° 26' W. on true line bet. Secs. 3 & 10	
39.76	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits, and deposited 1 pint of charcoal as per instructions.	
47.00	Road leading to the Columbia, brs. S.E.	
53.50	A steep, rocky, isolated bluff, 20 chs. long, rises on	