

## Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
	N. bet. Secs. 28 & 29	
14.00	N. division of Butter Creek, runs, N.E.	
19.50	Umatilla river, 1.50 lks. wide, runs, W., N.W.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.00	Set post for Cor. to Secs. 20, 21, 28 & 29, in mound with trench and pits and deposited 1 pint charcoal, as per instructions.	
	Soil; 3rd rate. Land; level and rolling	
	E. on random line bet. Secs. 21 & 28 Var. 20° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. and S. line, 50 lks. N. of the Cor. to Secs. 21, 22, 27 & 28, from which cor. I run, N. 89° 39' W. on true line bet. Secs. 21 & 28	
40.30	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.60	The Cor. to Secs. 20, 21, 28 & 29 Soil; 3rd rate. Land; rolling	
	N. bet. Secs. 20 & 21	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.00	Set post for Cor. to Secs. 20, 21, 17 & 16, in mound with trench and pits and deposited 1 pint charcoal as per instructions.	
	Soil; Sandy, 3rd rate. Land; gently rolling, grease and sage wood.	
	E. on random line bet. Secs. 16 & 21 Var. 20° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.25	Intersect N. and S. line, 45 lks. N. of the Cor. to Secs. 15, 16, 21 & 22, from which Cor. I run N. 89° 41' W. bet. Secs. 16 & 21	
40.12 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits & deposited 1 pint charcoal as per instructions.	
58.75	Enter willow undergrowth on bank of Umatilla.	