

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
80.00	Set post for Cor. to Secs. 4, 5, 8 & 9, in mound with trench & pits and deposited 1 pt. charcoal as per instructions. Soil; 3rd & 2nd rate, sandy, producing grass and sage. Oct. 23, 1860	
40.00	E. on random line bet. Secs. 9 & 4 Set post for temp. $\frac{1}{4}$ Sec. Cor. Var. 19° 55' E.	
80.02	Intersect N. & S. line, 85 lks. N. of the Cor. to Secs. 3, 4, 9 & 10, from which Cor. I run N. 89° 24' W. on true line bet. Secs. 4 & 9	
40.01	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits & deposited 1 pint of charcoal as per instructions.	
46.50	Umatilla river, 200 chs. wide, runs, N.E.	
67.50	Ascend bank, 20 ft. high	
80.02	The Cor. to Secs. 4, 5, 8 & 9 Soil; on Umatilla bottom, 1st rate, remainder 3rd rate. Land; rolling.	
40.00	N. on random line bet. Sec. 4 & 5 Set post for temp. $\frac{1}{4}$ Sec. Cor.	
81.52	Intersect 1st Stand. Parallel N., 5 lks. W. of the Closing Cor., for Secs. 4 & 5, from which Cor. I run S. 0° 2' W. bet. Secs. 4 & 5, on true line.	
41.52	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits, and deposited 1 pint of charcoal as per instructions.	
81.52	The Cor. to Secs. 4, 5, 8 & 9. Soil; 3rd rate. Land; rolling	
X	N. bet. Secs. 31 & 32 Ascend gradually	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 31, 32, 29 & 30, in mound with trench and pits and deposited 1 pint of charcoal as per instructions. Soil; 3rd rate, producing grass.	
	E. on random line bet. Secs. 29 & 32 Var. 20° E.	