

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.09	Intersect N. and S. line, 80 lks. N. of the Cor. to Secs. 28, 29, 32 & 33, from which Cor. I run N. 89° 26' W. on true line bet. Secs. 29 & 32.	
23.30	A division of Butter Creek, brs. N.E.	
40.04 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits, and deposited 1 pint of charcoal as per instructions.	
80.09	The Cor. to Secs. 31, 32, 29 & 30. <hr/> W. on random line bet. Secs. 30 & 31	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
76.79	Intersect W. Bdy. of Tp., 50 lks. S. of the Cor. to Secs. 25, 36, 30 & 31, from which Cor. I run S. 89° 38' E. on true line bet. Secs. 30 & 31	
36.79	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
76.79	The Cor. to Secs. 29, 30, 31 & 32. Soil; 3rd & 2nd rate. Land; level <hr/> N. on line bet. Secs. 29 & 30	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
52.75	Umatilla, 150 lks. wide, runs, N.W.	
80.00	Set post for Cor. to Secs. 19, 20, 29 & 30, in mound with trench and pits and deposited 1 pint of charcoal as per instructions. Soil; 3rd and 2nd rate. Land; level.	Oct. 24, 1860
		Oct. 25, 1860
	E. on random line bet. Secs. 20 & 29	Var. 19° 55' E
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. and S. line, 77 lks. N. of the Cor. to Secs. 20, 21, 28 & 29, from which Cor. I run N. 89° 27' W. on true line bet. Secs. 20 & 29	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.00	The Cor. to Secs. 19, 20, 29 & 30.	